



*Your Destination...Our Priority*

## Travel Times


# I-94 Clearwater to St. Cloud Unbonded Concrete Project

St. Cloud  
Aug. 26, 2013

ITS

## District 3

- 12 Counties
- Central Minnesota
- I-94 - 80 miles
- Baxter – headquarters
- St. Cloud – sub area



# I-94 Project

## Un-bonded Concrete Overlay

- SP 7380-238
- Concrete overlay
- Clearwater to St. Cloud
- Spring 2013
- 7.5 miles length
- \$16.5 M



## I-94 Traffic Volumes


- Average Daily Traffic (ADT)
  - 45,500 (M-Thur)
  - 55,000 (Average Weekends)
- Hourly volumes
  - Peak periods – 2,400 – 2,800 VPH
- Single Lane Capacity
  - 1,500 VPH – merge area
  - 1000 vehicles per hour over capacity

### ❖ Significant Delays/Backups


- Traffic Management Plan

## TH 94 WB Monthly Averages on Fridays

Assumed Detour Reduction of 10%



Assumed Capacity of 1500 and Detour Reduction of 10%



# Traffic Management Plan

- Significant Impact Project
- Traffic Management Plan (TMP)
  - 1 – Traffic Control Plans
  - 2 – Traffic Operations Plan
  - 3 – Public Information Plan
- TMP – revisit scope of project
  - Concrete – due to material life span

# Traffic Control Plans

## Un-bonded Concrete Project

- One lane traffic
- Crossovers
- Head-to-head traffic
- Ramp closures
- Detours
  - Ramps/loops/TH 24



## Construction Staging Un-bonded Concrete Project


- Prep work Fall of 2012
- April to June 2013 – least impact
  - Stage 1 – EB closed
    - April to Memorial
  - Stage 2 – WB closed
    - Memorial to July 4<sup>th</sup>
- 4-lane open Memorial Weekend
- 4-lane by July 4<sup>th</sup> Weekend

# ITS Project SP 8823-260 Traffic Operations


ITS – Separate project

## IWZ Tool Box

- I. Travel Time Info
- II. Stopped Traffic
- III. TH 24 Detour -
  - Dynamic
  - I-94 WB traffic  
30% exit TH 24
  - CSAH 75 detour



## ESTIMATED TRIP TIME




Consideration should be given to posting an alternate route and travel time for additional driver information.

- The CMS may be replaced with static warning signs equipped with two (2) CMS characters in dynamic mode. The characters would display the real-time travel time in the work zone downstream.
- Consideration should be given to posting an alternate route and travel time for additional driver information.
- The CMS may be supplemented with other informational devices such as Highway Advisory Radio (HAR).



### NOTES

- Advance warning signs and other standard temporary traffic control devices have not been shown on this figure. Refer to the M MUTCD including the 2007 Field Manual or the TTC Layout Templates for typical layout examples.
- All IWZ Guide Signs and CMS should be reviewed by the Mn/DOT Office of Traffic Safety, & Operations for design and message approval.
- Approved CMS messages should be listed in the Special Provisions, and approx CMS locations should shown on the TTC plans. All CMS displays should be blank when messages are not warranted.
- Refer to the Toolbox Definitions Section for graphic symbols and terms.



- The CMS may be replaced with an appropriate warning sign equipped with dynamically automated flashing lights as shown below.
- The static signs are spaced incrementally and the individual flashers are activated in response to queued traffic when the queue is detected within one mile of the sign location.



**OPTIONAL SIGN DESIGN**

- When traffic queue lengths are reasonably predictable, warning motorists of stopped / slowed traffic may be accomplished with the use of typical TTC warning signs placed prior to the anticipated beginning of queue.
- The system may be combined with "Dynamic Merge" and "Stopped Traffic Advisory" systems


## NOTES

- Advance warning signs and other standard temporary traffic control devices have not been shown on this figure. Refer to the MN MUTCD including the 2007 Field Manual or the TTC Layout Templates for typical layout examples.
- All IWZ Guide Signs and CMS should be reviewed by the Mn/DOT Office of Traffic, Safety, & Operations for design and message approval.
- Approved CMS messages should be listed in the Special Provisions, and approx CMS locations should be shown on the TTC plans. All CMS displays should be blank when messages are not warranted.
- Refer to the Toolbox Definitions Section for graphic symbols and terms.





*Your Destination...Our Priority*



**HONOR Service LEADERSHIP**

# ITS Procurement

## Travel Information System

### Procurement Methods

1. Request for Proposal (RFP)
2. In-House – State forces
3. Design/Bid/Build – selected
  - Hybrid System/Control – Why???
  - MnDOT – manage I-94 WB
  - Contractor – manage I-94 EB

## Design/Bid/Build

- Leverage existing infrastructure
  - St. Cloud east to Metro
    - Fiber network
    - Connected to RTMC
  - Detectors/Cameras/DMS
- St. Cloud west
  - Limited infrastructure


## Concerns

- Project costs – 20 detectors
  - I-35 Duluth 6 detectors/\$395,000
  - \$500,000 - ????
- Integration
- Accuracy of information – length





*Your Destination...Our Priority*



**HONOR Service LEADERSHIP**

# ITS Concept Plan Development

## 1. Travel Time

- 2 signs each direction
- 10 and 15 miles prior to project
- Detector spacing/mile (20 total)

## 2. Stopped Traffic Advisory

- CMS every 3 miles (8 total)
- 2 boards active prior to slow/stop point
- Common detection

## Concept Plan Development

### 3. TH 24 Dynamic Detour

- 1 CMS prior to Hasty interchange
- Activated when backups started
- Approx. 5 miles before project
- Backups – Hasty interchange
- Hasty exist heavily used
- 1000 vph less on I-94 WB peak times

## I-94 EB

### ITS contract

- Contractor responsible for EB
- Travel time at 17 & 10 miles
  - Hybrid signs – Static/Dynamic
  - Series 3 signs at 17 mile pt.
  - 1 Hybrid sign -10 mile point
- Stopped traffic Advisory
  - CMS every 3 miles

# I-94 EB

## 17 mile point





# I-94 EB

## 2<sup>nd</sup> sign



# I-94 EB

## 3<sup>rd</sup> Hybrid sign (17 mile pt.)



# I-94 EB

## Hybrid sign (10 mile pt.)





# Nonintrusive Detector

## 1 mile spacing



# I-94 WB

## Travel time (MnDOT)



# I-94 WB

## Travel time (MnDOT)





## Project Costs

- Much lower than expected
  - \$200,000 range
- 2 Bidders
- Safety Signs – awarded contract
  - ASTI subcontractor

## Data Collection


- Weekly data collected
  - Speeds
  - Travel times
  - Message content
    - Travel time postings
    - Stopped message posting
  - Compare to field information

Greater than 40 mph
Less than 40 mph, greater than 30 mph
Less than 30 mph, greater than 15 mph
Less than 15 mph

Eastbound Detector Speeds

	Avon				St. Joseph				TH 23				TH 15				CSAH 75			
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q11	Q12	Q13	Q14	Q15	Q16	Q17	Q18			
6/14/13 2:00 PM	73	69	73	74	76	69	67	73	71	70	72	74	70	20	46	57	59			
6/14/13 2:15 PM	73	68	74	75	77	70	69	73	72	70	71	74	70	21	37	58	57			
6/14/13 2:30 PM	74	69	73	73	76	70	68	73	72	71	72	75	46	19	36	57	57			
6/14/13 2:45 PM	74	69	76	76	78	70	69	74	73	71	72	76	23	19	40	59	57			
6/14/13 3:00 PM	73	68	73	73	78	71	69	74	73	71	72	75	27	16	48	59	58			
6/14/13 3:15 PM	73	68	74	75	78	71	68	73	72	72	73	75	34	20	33	59	58			
6/14/13 3:30 PM	73	67	74	74	78	70	68	73	73	71	71	75	16	15	32	60	47			
6/14/13 3:45 PM	73	68	73	74	74	69	68	73	72	71	72	75	12	20	32	57	55			
6/14/13 4:00 PM	72	67	73	74	76	69	67	72	72	71	72	73	13	13	24	50	50			
6/14/13 4:15 PM	72	68	74	74	77	70	68	73	72	70	71	75	28	19	11	10	33			
6/14/13 4:30 PM	73	68	74	74	73	70	68	73	72	70	71	74	7	8	14	16	33			
6/14/13 4:45 PM	74	69	73	74	78	70	68	73	73	71	72	69	4	12	20	17	26			
6/14/13 5:00 PM	74	69	73	73	76	70	68	73	72	72	72	51	9	13	22	19	32			
6/14/13 5:15 PM	74	70	73	76	77	70	68	74	73	71	72	26	7	13	23	16	34			
6/14/13 5:30 PM	74	69	74	73	77	70	68	73	73	71	73	28	10	14	27	23	32			
6/14/13 5:45 PM	74	70	73	74	78	69	68	73	72	72	72	65	6	12	22	17	32			
6/14/13 6:00 PM	74	70	76	76	80	70	69	73	74	71	73	50	7	17	35	28	33			
6/14/13 6:15 PM	73	69	74	76	78	69	67	73	73	72	73	56	12	19	39	13	32			
6/14/13 6:30 PM	74	70	76	73	76	70	70	73	71	71	72	68	5	12	40	12	31			
6/14/13 6:45 PM	74	70	76	73	76	71	69	73	73	72	73	57	14	22	39	13	33			
6/14/13 7:00 PM	74	70	73	76	77	71	69	73	72	72	72	74	19	10	32	14	33			
6/14/13 7:15 PM	74	70	73	73	76	71	69	74	73	71	73	76	33	10	27	18	34			
6/14/13 7:30 PM	74	70	73	77	78	70	69	74	74	72	74	75	64	15	39	18	33			
6/14/13 7:45 PM	74	70	76	76	78	72	69	74	74	71	74	75	71	19	35	12	36			
6/14/13 8:00 PM	74	70	76	76	76	71	68	73	73	72	72	74	71	11	43	15	34			
6/14/13 8:15 PM	74	70	77	73	79	72	70	74	73	72	73	76	71	63	50	16	36			
6/14/13 8:30 PM	74	70	73	74	76	71	70	74	74	72	75	75	73	63	50	14	37			
6/14/13 8:45 PM	74	70	76	77	79	72	70	74	73	72	73	74	71	64	63	27	32			
6/14/13 9:00 PM	74	68	73	73	77	71	69	74	73	72	72	74	71	64	72	64	36			
6/14/13 9:15 PM	73	68	76	73	76	69	67	73	72	72	73	74	71	66	73	64	50			
6/14/13 9:30 PM	74	68	74	73	76	70	69	73	72	71	72	75	71	66	72	62	46			
6/14/13 9:45 PM	72	68	72	72	74	69	68	73	72	70	72	72	71	64	72	61	41			
6/14/13 10:00 PM	72	68	74	73	73	70	68	71	70	71	72	74	70	66	74	59	59			
6/14/13 10:15 PM	71	68	73	72	74	68	69	72	70	70	72	72	71	63	73	59	62			
6/14/13 10:30 PM	72	69	74	76	78	69	68	73	71	70	71	74	71	63	72	60	63			
6/14/13 10:45 PM	73	68	74	73	78	70	66	73	72	71	72	75	71	63	73	63	62			
6/14/13 11:00 PM	71	68	74	74	73	67	68	72	70	71	72	73	70	67	72	62	63			

### Travel Time TT17 Friday 6/14/2013



## Project Findings

- Integration – smoother than expected
- Contractor - open to improvements
- Backups less the expected
- Diversion of traffic – up to 1000 vph
  - TH 24 detour
  - TH 10 – good parallel route WB
  - CSAH 75 parallels I-94
  - Limited public complaints



# Project Findings

- Improvements:
  - Speed variations during hour
  - Contractor's web site
    - Hybrid signs – Display ???



*Your Destination...Our Priority*

# Questions

ITS