



Jon Jackels, SRF Consulting Group

Intersection Conflict Warning Systems (ICWS)

Rural and Small Community Traffic Management Technology


Safety Challenges





Traditional Improvements

Indirect Turns




Roundabouts



Stop Sign Beacons




Intersection Conflict Warning Systems (ICWS)




MnDOT RICWS System Operation – Major Road Warning

- Major Road warning active when vehicles are in the **red** zone.



MnDOT RICWS System Operation – Minor Road Warning




- Minor Road warning active when vehicles are in the **red** zone.



History of ICWS in Minnesota

- Intersection Decision Support (IDS)
- Cooperative Intersection Collision Avoidance System (CICAS)
- Intersection Warning System (IWZ)
- Safe Intersections
- Rural Intersection Conflict Warning System (RICWS)
- Advanced LED Warning System (ALERT2)
- Mainline Dynamic Warning System (MDWS)
- Local RICWS Project



National Effort to Study ICWS

ENTERPRISE Transportation Pooled Fund


- Foundation for Architectural Review & Systems Engineering
- Design Decisions
- Testing and Validation Results
- Maintenance Logs

RICWS Maintenance Log
Last Update: 6/26/2012

Site No.	Site Location/Name	Observed Component Failure and/or Symptoms	Date Reported By	MODOT File Number (date)	Contractor Name (date)	Diagnosis	Date of Repair	Components replaced or repaired	Notes to prevent future failures	Repair Performed By (Organization and Personnel)	Maintenance Activities (hours spent, replacement equipment used, license generated)	Duration between Contractor Notification and Restoration (days)
1	Albin (TH 42 and CSAN 12)	Site not working properly	Albin County Engineer	12/30/2011	12/27/11	Utility sensitivity was set too high on one of the cars.	12/30/2011	Diagnosed, retested, power cycled	Verify that loop sensitivity is set properly before turn-in test.	Origin, Design Electric	3 hours	0
2	Eggle (TH 42 and CSAN 8)	The system was in trouble for 10 days and was not flashing as it should on CSAN 8	Jim Homan, MODOT Engineering Specialist	6/13/2014	6/18/14	System was not flashing, check and design electric provide the contractor design sign on the site on 6/18/2014	6/18/2014	Diagnosed, retested, power cycled	None	Jim Homan, MODOT Engineering Specialist	Not available	Not applicable
3	Duval (TH 3 and CSAN 35)	The signs are flashing consistently on TH 3 and do not flash as it should on CSAN 35	Jim Homan, MODOT Engineering Specialist	6/5/2014	6/5/14	System was not flashing, check and design electric provide the contractor design sign on the site on 6/5/2014	6/18/2014	Diagnosed, retested, power cycled	None	Jim Homan, MODOT Engineering Specialist	Not available	Not applicable
4	Eggle (TH 42 and CSAN 8)	The system was in trouble for 10 days and was not flashing as it should on CSAN 8	Jim Homan, MODOT Engineering Specialist	6/13/2014	6/20/14	Diagnosed, retested, power cycled	6/20/2014	Diagnosed, retested, power cycled	Remove protective coating on the back of the loop detector on CSAN 8. This system is not flashing as it should on CSAN 8. Design electric provide the contractor design sign on the site on 6/20/2014	Design electric, other personnel	0-1/2 hours	0
33	Land (MOHW 47 & CSAN 8)	System was in trouble mode (the lights out signs were dark, and the lights on mainline were flashing continuously)	Chris Erickson, MODOT Metro	12/13/2014	12/13/2014	Unusual detection behavior also programmed as it could not and just system's failure	12/16/2014	Not applicable	None	Don Brink, Design Electric	1/4 hour	1 day
35	Marshall (MHW 23 & CSAN 30)	One of the flashing sections was "flashing off" because of a sign error	Don Brink, Design Electric	6/23/2014	6/23/14	Loop not loose	7/1/2014	Reattached lead	Consider attachment method. Photo program becomes more prevalent.	Don, Design Electric	15 minutes	0
36	Marshall (MHW 23 & CSAN 30)	Median detector has intermittent and stuck off	Walt James, SRF Inspector	6/24/2014	6/24/14	Detector card sensitivity not to calibration	6/24/2014	Adjusted sensitivity on Design electric	Detector card sensitivity on Design electric	Don, Design Electric	1 hour	1
37	Eggle (TH 42 and CSAN 8)	System was in trouble mode	Originals reported by public, verified by Don Brink	6/30/2014	6/30/14		6/30/2014	Diagnosed, retested, power cycled	Diagnosed, retested, power cycled	MODOT DE	Not available	Not applicable
38	Marshall Station	Major road flashes are not working	Jim Johnson, Design Electric	7/8/2014	7/8/2014	Customer needs to be programmed to allow for wig-wag operation	8/28/2014	Diagnosed, retested, power cycled	Program contractor upon install	Design Electric		
39	Duval (TH 3 and CSAN 35)	Not working properly	Jim Homan, MODOT Engineering Specialist	6/13/2014	6/18/14	Design sign not installed on CSAN 35	6/25/2014	Diagnosed, retested, power cycled	Verify installation upon installation	Don, Design Electric	1-1/4 hours	1
34	Duval (TH 42 and CSAN 8)	The system was in trouble for 10 days and was not flashing as it should on CSAN 8	City of Jacksonville	7/7/2014	7/7/2014	Insensitivity on the loop B-2	7/9/2014	Diagnosed, retested, power cycled	Standard to add programming or adjust the loop B-2	Don, Design Electric	2 hours	2
37	Eggle (TH 42 and CSAN 8)	System not working	Don Brink	7/13/2014	7/13/2014	One Design electric	7/13/2014	Diagnosed, retested, power cycled	Diagnosed, retested, power cycled	Don, Design Electric	1.5 hours	0




Safe Intersection



MnDOT's Rural Intersection Conflict Warning System (RICWS) Project

- 50+ Deployments, 3 years operation
- Project Findings
 - Safety improved (35 to 45%)
 - Standard equipment for ease of maintenance (once/year)
 - Systems are reliable
 - Detection accuracy and driver confidence (99.98%)
- Additional 350+ Sites Identified
 - At discretion of Districts

Rural Intersections Conflict Warning System (RICWS)



RCI	D1	D2	D3	D4	M	D6	D7	D8	Total
CRSP List	23	3	38	15	30	15	6	16	146
Constructed	12	2	15	7	17	5	12	6	64



CRSP - County Road Safety Plan

0 12.5 25 50 75 100 Miles

January - 2018


RICWS Components

- Detection
 - Canoga Micro Loops
 - Loop Detectors
- Controller
 - Econolite ASC/3
- Signs
 - Blank Out
 - Static



ALERT 2

- Advanced LED Warning System for Rural Intersections




Mainline Dynamic Warning System



St. Louis County, MN – “Local” RICWS Project

- “Local” RICWS Project Goals
 - Lower cost
 - Easier to operate and maintain
 - Reliable
 - Minimize underground locate requests
 - Can be leveraged by other counties






“Local” RICWS Project Team

- Technical panel to lead project:
 - Vic Lund (St. Louis County)
 - Guy Kohlnhofer (Dodge County)
 - Tim Bray (Crow Wing County)
 - Karin Grandia (Itasca County)
 - Mark Vizecky (MnDOT State Aid)
 - Rick West (Ottertail County)
 - Jodi Tech (Stearns County)
 - Taek Kwon (UMD)
 - Joe Gustafson (Washington County)
 - Sara Buermann (Wright County)
 - Chad Hausmann (Wright County)
 - Virgil Hawkins (Wright County)

“Local” RICWS Systems Engineering Approach

- Architectural Review
- Concept of Operations
- Systems Requirements
- System Design
- Construction
- Project Documentation

- Intersection Location
 - County Hwy 25 & County 16



Architectural Review – Overall Process

- ENTERPRISE Transportation Pooled Fund
- Literature search into ICWS effectiveness (sign type, wording, driver perception, etc.)
- Leverage relationships with agencies that have ICWS
- Broad survey of agencies that have ICWS

Architectural Review – State DOT Outreach


- National search for existing systems

- System components

- Make and model of components
- Controller types and capabilities
- Sign choice
- Detector technology
- Communication
- Power

- Notable issues and overall cost

- Future upgrades or deployments





Survey Findings (61 responses)

Survey Topic:

1. Include Minor Road Alert
2. Underground Components
3. Solar Power
4. Maintenance
5. System Cost
6. Remote Monitoring


Response:

1. Depends on site conditions
2. Local agencies prefer to minimize
3. Interested if reliable
4. Want option to maintain with own staff
5. Cheaper is better
6. Important as long as low cost

Conclusions:



- Findings align with project goals
- Open to solar, detection, and wireless to reduce cost
- Remotely monitor for MnDOT support

Systems Engineering - Conceptual Design



Local” RICWS Project Approach – Next Steps

- Finalized Systems Engineering
 - Concept of Operations
 - System Requirements
- Completed System Design
 - Project has be let, not awarded
- System Deployment





Jon Jackels, SRF Consulting Group

Thank you!

jjackels@srfconsulting.com | (763) 249-6722